

BID FORM
LASCHEN PARK

Item / Description	Approx. Qty	Unit	Unit Price	Subtotal
2. Furnish and install erosion control fencing as shown on plan. See detail.	366	linear feet	_____	_____
3. Furnish and install construction entrance as shown on plan. See detail.	X	lump sum	_____	_____
4. Furnish and install inlet protection.	210	linear feet	_____	_____
SUBTOTAL				<div style="border: 1px solid black; width: 150px; height: 30px;"></div>

D. SITE GRADING:

1. Placement and compaction of additional CA-6 to obtain grades as shown in the drawings to accommodate improvements.	X	lump sum	_____	_____
2. Fine grading to achieve grades within landscape areas.	X	lump sum	_____	_____
SUBTOTAL				<div style="border: 1px solid black; width: 150px; height: 30px;"></div>

E. CONCRETE

1. 4" thick fiber reinforced concrete walk.	661	square feet	_____	_____
SUBTOTAL				<div style="border: 1px solid black; width: 150px; height: 30px;"></div>

Item / Description	Approx. Qty	Unit	Unit Price	Subtotal
F. TENNIS/PICKLEBALL COURTS				
1. Hot Mix Asphalt Court Pavement:				
a. Furnish and install HMA surface course, binder course, and recompact existing aggregate base. Install aggregate as needed to fulfill grading requirements. See detail and specifications.	1,893	square yards	_____	_____
b. Apply Court acrylic color surface coating by Elite Sport Coating or approved equal. Minimum 2 coats plus all line painting (minimum 2 coats). Install surface coating and line paint per manufacturer's recommendations.	X	lump sum	_____	_____
3. Furnish and install tennis posts #2201-11P, tennis net #8353, and net tie-down #8371-30 by Patterson Williams or approved equal with sleeve and cap #8303-24-2N	2	each	_____	_____
4. Furnish and install 10' high black vinyl coated chain link fencing including posts, rails and fence fabric as shown and noted on the plan. Posts shall be pile-driven.	644	linear feet	_____	_____
5. Furnish and install 3' wide x 7' high black vinyl coated pedestrian gate with transom.	3	each	_____	_____
6. Furnish and install 10' wide black vinyl coated maintenance gate.	1	each	_____	_____
7. Furnish and install 4' high black vinyl coated chain link fencing including posts, rails and fence fabric as shown and noted on the plan.	36	linear feet	_____	_____
8. Furnish and install 5' wide black vinyl coated pedestrian gate.	1	each	_____	_____
9. Reinstall existing backboard/bang wall.	1	each	_____	_____
10. Furnish and install pickleball posts #2202-20 and net #8354 by Patterson Williams or approved equal with sleeve and cap #8303-24-2N	2	each	_____	_____
SUBTOTAL				<div style="border: 1px solid black; width: 150px; height: 40px; margin: 0 auto;"></div>

Item / Description	Approx. Qty	Unit	Unit Price	Subtotal
--------------------	----------------	------	------------	----------

G. LAWN RESTORATION:

1. Fine grade, fertilize and seed all areas using a blended bluegrass seed (Clesen Premium Mix) as shown on the plans as supplied by Arthur Clesen Inc. or approved equal. Install with erosion control blanket. Apply at rate 5-6 lbs. per 1,000SF. See specifications.

0.36

acres

SUBTOTAL

SUBTOTAL FOR SITE IMPROVEMENTS

ALTERNATE BID ITEMS

Alternate #1: Fence/Concrete Band Detail

1. Install fence posts with footing and 12" wide concrete band as detailed.

644

linear feet

Alternate #2: Bangwall/Backboard

1. Furnish and install bangwall/backboard Model #34856 by Douglas or approved equal.

1

each

BID FORM
LASCHEN PARK

Item / Description	Approx. Qty	Unit	Unit Price	Subtotal
--------------------	----------------	------	------------	----------

UNIT PRICES

The following unit prices will be used to establish costs for changes to the contract. Provide the following unit prices based on the plans, details and specifications.

1. Surplus material hauled off site.	50	cubic yard		
2. Remove unsuitable soils and dispose of off-site and provide 6-in clean black screened topsoil	50	cubic yard		
3. Topsoil	50	cubic yard		
4. Tree Removal 4" - 6" caliper.	1	each		
5. Tree Removal 7" - 9" caliper.	1	each		
6. Tree Removal 10" - 12" caliper.	1	each		